



Building and Infrastructures

It is the infrastructure that contains our datacenters. The problems we face are cooling, recovery and failure and power distributions.

BUILDING AND INFRASTRUCTURE



The main components of a typical data center



DATA CENTER POWER SYSTEMS: In order to protect against power failure, battery and diesel generators are used to backup the external supply. The UPS typically combines three functions in one system:

- contains some form of energy storage (electrical, chemical, or mechanical) to bridge the time between the utility failure and the availability of generator power
- contains a transfer switch that chooses the active power input (either utility power or generator power)
- conditions the incoming power feed, removing voltage spikes or sags, or harmonic distortions in the AC feed

DATA CENTER COOLING SYSTEMS: IT equipment generates a lot of heat: the cooling system is usually a very expensive component of the datacenter, and it is composed by coolers, heat-exchangers and cold water tanks.


Free cooling, i.e., open-loop, refers to the use of cold outside air to either help the production of chilled water or directly cool servers. It is not completely free in the sense of zero cost, but it involves very low-energy costs compared to chillers

Closed-loop systems come in many forms, the most common being the air circuit on the data center floor


- The goal is to isolate and remove heat from the servers and transport it to a heat exchanger
- Cold air flows to the servers, heats up, and eventually reaches a heat exchanger to cool it down again for the next cycle through the servers

Closed-loop with two loops

- ✓ The airflow through the underfloor plenum, the racks, and back to the CRAC (a 1960s term for *computer room air conditioning*) defines the primary air circuit, i.e., the **first loop**
- ✓ The **second loop** (the liquid supply inside the CRACs units) leads directly from the CRAC to external heat exchangers (typically placed on the building roof) that discharge the heat to the environment




A three-loop system commonly used in large-scale data center



Each topology of cooling system presents tradeoffs in complexity, efficiency, and cost:

- Fresh air cooling can be very efficient but does not work in all climates, requires filtering of airborne particulates, and can introduce complex control problems
- Two-loop systems are easy to implement, relatively inexpensive to construct, and offer isolation from external contamination, but typically have lower operational efficiency
- A three-loop system is the most expensive to construct and has moderately complex controls, but offers contaminant protection and good efficiency

Container based Datacenter



Container-based data centers go one step beyond in-row cooling by placing the server racks inside a container (typically 6 to 12 mt long) and integrating heat exchange and power distribution into the container as well.

Datacenter built inside a container in so you can have everything in a confined space. This solution can also be moved freely as it is capable to be contained in a container.

Datacenter consumption


The datacenter consumption is really high, the power needed and CO_2 emitted is similar to the one of England.

We use a metric for measure the impact of a datacenter:

$$PUE = \frac{TotalFacilityPower}{ITEquipementpower}$$

The datacenter efficiency is measured as DCiE and is the inverse of the PUE.

AVERAGE PUE OF LARGEST DATA CENTER




2012 Study



| PUE | DCiE | Level of Efficiency |
|-----|------|---------------------|
| 3.0 | 33% | Very Inefficient |
| 2.5 | 40% | Inefficient |
| 2.0 | 50% | Average |
| 1.5 | 67% | Efficient |
| 1.2 | 83% | Very Efficient |

Continuous PUE Improvement
Average PUE for all data centers



Datacenter Tiers

| Tier Level | Requirements |
|------------|---|
| 1 | <ul style="list-style-type: none">• Single non-redundant distribution path serving the IT equipment• Non-redundant capacity components• Basic site infrastructure with expected availability of 99.671% |
| 2 | <ul style="list-style-type: none">• Meets or exceeds all Tier 1 requirements• Redundant site infrastructure capacity components with expected availability of 99.741% |
| 3 | <ul style="list-style-type: none">• Meets or exceeds all Tier 2 requirements• Multiple independent distribution paths serving the IT equipment• All IT equipment must be dual-powered and fully compatible with the topology of a site's architecture• Concurrently maintainable site infrastructure with expected availability of 99.982% |
| 4 | <ul style="list-style-type: none">• Meets or exceeds all Tier 3 requirements• All cooling equipment is independently dual-powered, including chillers and heating, ventilating and air-conditioning (HVAC) systems• Fault-tolerant site infrastructure with expected availability of 99.999% |